

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 51N R 36W	C5
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 19 T 51N R 36W	11
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		



I, Stephan J. Szyszkoski, in a field survey on C5 09/13/2010  
11 09/22/2010 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5			●										
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9	●												
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

(C5) Corner common to Sections 7-8-17-18. 1959 - Corner remonumented by Billy D. Buckler RLS from local evidence. Set 1" pipe with 4" brass cap. 8" Cedar N05W 49 links, 9" Hemlock N52E 40 links, 15" Sugar Maple S56E 44 links.

(11-Sec. 19) Southwest 1/16 corner, Section 19. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(C5) Found the 1959 monument in good condition and at record bearing and distance from the 1959 Cedar and Hemlock NBTs, both in good condition, and from the NBT Sugar SE, standing dead with scribing plain. Accepted the monument as the best available evidence of the position of the original corner.

(11-Sec. 19) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(C5) Fd. 1"ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:  
12" Cedar N03E 32.9' old marks (1959 NBT)  
12" Hemlock N57E 26.7' overgrown do  
7" Maple S35E 36.5' mrkd "S17 NBT"  
11" Hemlock S86W 20.0' "S18 NBT"  
Scribed Y.Birch tree and Hemlock tree, standing dead, face the corner. Bearings are magnetic. Cedar post adjacent.

(11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
4" Maple N09E 16.6' mrkd "1/16S BT"  
10" Cedar N86E 16.7' do  
9" Cedar S14W 13.05' do  
5" B.Ash N80W 11.6' do  
Set sq'd cedar post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 01/06/2011



For the Michigan Department of Natural Resources and Environment, Forest Management Division