

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County)	Located In:	Corner Code #
1. Public Land Survey	T 51N R 36W	E10
	T R	
	T R	
2. Property Controlling in Section	S 28 T 51N R 36W	10
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 10 06/05/2012 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E10) Quarter corner common to Sections 28 and 29. 1848 - Established by S.W.Higgins Deputy Surveyor midway and on the Section line between Section corners 40.00 ch. north and south. Set post. Hemlock 20" N10W 14 links, Cedar 18" S30E 25 links. 1962 - Billy D. Buckler RLS remonumented the corner at the position of 2 wood posts found at record bearing and distance from the remains of the Cedar BT S30E 25 links. Buckler also found the original Cedar line tree 1.48 chains north to correspond with the record field notes. Set 1" pipe with 4" brass cap. 12" Y.Birch S25E 32 links, 11" Cedar N60W 81 links.

(10-Sec. 28) South 1/16 corner between Sections 28 and 29. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E10) Found the 1962 monument in good condition and at record bearing and distance from the 1962 witnesses. The Y.Birch is now a mass of rotted wood. The Cedar N60W is in good condition with old upper and lower blazes. Found old rotted wood post laying on ground and a post point adjacent to the monument. Accepted the monument as a careful and faithful perpetuation of the position of the original corner. Found distances to adjacent Section corners to be 2625.51' south and 2530.59' north.

(10-Sec. 28) Established the position for the corner midway and on the Section line between Section corner 1312.76' south and Quarter corner 1312.76' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E10) Found 1"ID I.pipe with 4" brass MI Dept. of Conservation cap.
Set measuring nail with MDNR tag in the side of:
13" Cedar N47W 53.7' old blazes (1962 NBT)
10" Cedar N66E 26.3' mrkd "1/4S NBT"
5" Y.Birch S14E 12.9' do
8" Hemlock S50W 10.1' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

(10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
3" B.Ash N70E 7.6' mrkd "1/16S BT"
9" Cedar S63E 7.9' do
4" Cedar S53W 14.3' do
7" Cedar N49W 18.3' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 07/11/2012

For the Michigan Department of Natural Resources, Forest Resources Division

