

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 35W T 52N R 35W T _____ R _____	D9 E11 _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____ S _____ T _____ R _____	_____ _____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Stephan J. Szyszkoski, in a field survey on 04/27/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D9) Quarter corner common to Sections 20 and 29. 1953 - Remonumented by Billy D. Buckler RLS in the
original position from one original B.T. found in place, in good condition. Set 1" pipe with 4"
brass cap. 8" Hard Maple S02W 59 links, 6" Hard Maple N84E 52 links. 1995 - Rewitnessed by the
undersigned: Found 1" pipe with 4" brass MI Dept. of Conservation tablet. The 1953 witnesses were
not recovered. Blazed and scribed the following: 10" Sugar S35W 24.9', 8" Sugar N57W 22.8', 12"
Sugar S74E 22.5', 5" Sugar N52E 32.0'.

(E11) Corner common to Sections 28-29-32-33. 1953 - Billy D. Buckler RLS remonumented the corner in
the original position from one original B.T. still in place, in poor condition. Set 1" pipe with 4"
brass cap. 14" Hard Maple S40E 61 links, 14" Y.Birch N62W 19 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D9) Found the 1953 monument of record in good condition and at record bearing and distance from the
1995 witnesses, all in good condition except the Sugar S35W which is dead and down. Left the
monument in place and made new witnesses as described below.

(E11) Found the 1953 monument set firmly, with a portion of the brass cap broken away. At record
bearing and distance, I found the 1953 NBT Sugar S40E 61 links. Found three other trees nearby with
nearly overgrown upper and lower blazes and markings scribed into the blazes, apparently with a
knife, not of record, probably made by a local forester. Accepted the monument as a careful and
faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D9) Fd. 1" pipe with 4" brass MI Dept. of
Conservation tablet. Set measuring nail
with MDNR tag in the side of:
11" Sugar N51W 22.95' old marks 1995 NBT
13" Sugar S80E 22.8' do do
7" Sugar N49E 32.05' do do
7" Sugar S28W 41.85' mrkd "1/4S NBT"
Set sq'd Cedar post adjacent.
Bearings are magnetic.

(E11) Fd. 1" ID I. pipe with broken brass MI
Dept. of Conservation tablet.
Set measuring nail with MDNR tag in the side of:
19" Sugar S37E 39.85' old blazes 1953 NBT
13" Hemlock S70E 38.55' fd. blazes and marks
11" Sugar N42W 7.9' do
11" Hemlock S84W 24.95' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 08/01/2011

For the Michigan Department of Natural Resources, Forest Management Division

