

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County)	Located In:	Corner Code #
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 13 T 52N R 35W	L6
	S 13 T 52N R 35W	4
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 4 08/09/2010 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L6) Center of Section 13. Corner not established in the original survey. Previously established by
an unknown surveyor at an unknown time in the past. Local land owner William Bingham remembers
seeing an iron marker at the corner position in the center of Peltola road and in line with old fence
lines to the north and south.

(4-Sec. 13) Northwest 1/16 corner, Section 13. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L6) Found no monumentation at the corner position. Reestablished the corner at the intersection of
old fence lines north, south, and west. This position also falls in the center of gravelled Peltola
road to the east. The position has plainly been accepted by local land owners for many years,
judging by the appearance of the fences and the local land use. Furthermore, this position had
evidently been used by an unknown surveyor long ago to subdivide the NE1/4 of Section 14, as the
conforming locations of old fence lines running between 1/16 corner positions #5, 6, and #9 suggest.
I accept the long-used position as the Center of Section 13 and note that from this position the
intersection of straight lines connecting opposite 1/4 corner of this Section is 3.3' East and 37.4'
South.

(4-Sec. 13) Established the corner at the intersection of straight lines connecting opposite 1/16
corners. The corner position is 2 ft. south of the flowing water of a creek.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap
buried 7" below the gravel surface of Peltola Rd.
Set measuring nail with MDNR tag in the side of:
4" Sugar N38E 27.45' mrkd "C1/4 BT"
7" Sugar S23E 58.65' do
4" Sugar S06W 40.25' do
8" triple Maple N44W 33.5' do
Bearings are magnetic.

(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
4" Y.Birch S46W 28.9' mrkd "1/16S BT"
16" Hemlock S31W 33.65' do
4" Spruce S08W 17.5' do
6" Cedar S22E 30.05' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 10/20/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

