

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 35W	G13
	T R	
	T R	
2. Property Controlling in Section	S 21 T 52N R 35W	F8
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on G13 11/12/2009 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G13) Section corner common to 33-34 T52N-R35W and 3-4 T51N-R35W. 1845 - Established by Wm.A.Burt
Deputy Surveyor. Set post. Y.Birch 8" N16E 39 links, Hemlock 22" N15W 7 links. 1848 - Additional
NBTs by S.W.Higgins, Deputy Surveyor. Balsam 10" S20E 32 links, Hemlock 14" S55W 29 links. Notes of
P.A. and M.C.Larsen: "1922 - Set cedar post from B.T. Birch". 1953 - Dean C. DeLaMater RLS
remonumented the corner: "Corner had been previously located by unknown Surveyor. Checks OK by
proportionate measurement. Remains of two probable B.T.s still in place, badly rotted. Set 1" pipe
with 4" brass cap. 10" Hemlock S24E 78 links, 10" Y.Birch N72W 39 links".

(F8) Center of Section 21. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G13) Found the 1953 monument in good condition and at record bearing and distance from the 1953
NBTs. The Hemlock SE is in good condition with overgrown blazes. The Y.Birch is dead and leaning.
Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(F8) Established the corner at the intersection of straight lines connecting opposite Quarter corners
of record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G13) Found 1"ID I.pipe with 4" brass MI Dept.
of Conservation cap. Set measuring nail with
MDNR tag in the side of:
14" Hemlock S15E 51.9' old blazes 1953 NBT
4" Sugar N33E 26.6' mrkd "S34 NBT"
7" Maple in clump S17W 13.6' "S4 NBT"
8" Maple w/poster N40W 9.9' "S33 NBT"
Set sq'd Cedar post adjacent.
Bearings are magnetic.

(F8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
11" Maple S83E 15.1' mrkd "C1/4 BT"
10" Sugar S20E 7.55' do
4" Sugar S71W 13.2' do
12" Sugar N54W 11.4' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11/17/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

