

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 36W T R T R	D9 (GCDB 240300)
2. Property Controlling in Section	S 21 T 52N R 36W S T R S T R	6 (GCDB 360360)
3. Miscellaneous Property in Sec.	S T R S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 10/03/13 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D9) Quarter corner common to Sections 20 and 29. 1963 - Billy D. Buckler RLS found and accepted a 1-1/4" ID iron pipe set by unknown party. New witnesses: 7" Elm S53°W 09 links, 8" Elm N70°E 12 links.

(6-Sec. 21) Northeast 1/16 corner, Section 21. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D9) Found a 1-1/2" ID iron pipe, projecting about 18" above ground, in good condition. The 1963 witnesses were not recovered. Found similar 1-1/2" iron pipes at 1/16 corners to the east and west, substantially midway and on the section line between D9 and E9 and C9, respectively, corroborating the position. I accept the pipe as the best available evidence of the position of the original corner.

(6-Sec. 21) Established the position for the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D9) Found 1.5" ID iron pipe.
Set measuring nail with MDNR tag in the side of:
10" Maple N09°E 1.75' mrkd "1/4S NBT"
12" Maple S25°E 27.45' do
4" Sugar S35°W 5.1' do
6" Ash N73°W 26.1' do
Set sq'd cedar post adjacent.
E= 7855153.609 N= 234811.067

(6) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
5" Y.Birch N27°E 19.4' mrkd "1/16S BT"
3" Maple S76°E 14.75' do
8" Sugar S43°E 15.65' do
5" Balsam S81°W 10.6' do
Set sq'd cedar post adjacent.
E= 7857220.176 N= 236069.165

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)
Coord. Ref.=NGS PID RL0502: N= 234995.272 m. E= 7857774.766 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11/18/2013

For the Michigan Department of Natural Resources, Forest Resources Division



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 7, 1971

Revised Jan., 1983

Revised Oct., 1995