

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County)	Located In:	Corner Code #
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 4 T 53N R 32W	C-W-E-NW 1/256
	S 4 T 53N R 32W	AMC E. of F2
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4			3		2		1	
3													
4	7		8		9			10		11		12	
5													
6	18		17		16			15		14		13	
7													
8	19		20		21			22		23		24	
9													
10	30		29		28			27		26		25	
11													
12	31		32		33			34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on AMC 04/25/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C-W-E-NW 1/256 corner) Being the NW corner of the East 3/4 of the SE1/4 of the NW1/4 of Section 4.
Not established in the original survey.

(AMC E. of F2) Auxiliary Meander Corner at the shore of Lake Superior on the E-W 1/4 line of Section
4. 1978 - Established by K.L.Sackett RLS #19006. Set 1"ID I.pipe with 4" aluminum cap. 13" Maple
N60W 3.2', 10" Cedar N09W 19.3', 5" Balsam N38E 15.2'. 2010 - Jeffrey J. West PS #46697 did not
recover the 1978 monument, it having been destroyed by the eroding bank along Lake Superior. Mr.
West recovered one of the three 1978 witnesses and, in conjunction with existing monumentation on the
E-W 1/4 line to the west, reestablished the E-W 1/4 line in the 1978 position and placed a new
auxiliary meander corner on that line 745.94' east of the monumented Center of Section 4. He set a
5/8" pin with plastic cap #46697.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C-W-E-NW 1/256) Established the corner on a straight line between 1/16 corner #4 329.76' west and
the unmonumented 1/16 corner #5 989.28' east.

(AMC E. of F2) Found the 2010 monument in good condition and in accord with existing monumentation
along the E-W 1/4 line of Section 4. I found the 2010 monument 745.86' east of the monumented Center
of Section 4 and accepted same as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1/256) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
The cap is stamped to show current land ownership,
private lands to the SW, the balance being public.
Set measuring nail with MDNR tag in the side of:
8" Y.Birch N14E 22.55' mrkd "PC BT"
8" Cedar S84E 12.05' do
6" Maple S14E 8.5' do
5" twin Maple S62W 1.4' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

(AMC) Found 5/8" rebar with plastic cap stamped
"UPEA JJW 46697", projecting 6" above ground.
Set measuring nail with MDNR tag in the side of:
4" Balsam N36E 23.55'
9" Y.Birch N75E 12.45'
4" Balsam S44W 26.95'
5" Balsam N23W 13.6'
Set sq'd Cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 06/20/2011

For the Michigan Department of Natural Resources, Forest Management Division

