


LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 20 T 55N R 31W	Special Meander corner north of #8 (SMC)
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S 20 T 55N R 31W	Aux. Meander corner north of #8 (AMC)
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number



NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Special Meander corner north of #8 - The intersection of the West 1/16 line of Section 20 with the 1845 GLO meander of Little Rice Lake (Lake No. 2). Not previously monumented.

Auxiliary Meander corner north of #8 - The intersection of the partition line between Government Lots 6 & 7 with the south shore of Little Rice Lake. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SMC - Established the W1/16 line as a line running northerly from the W1/16 corner at a bearing which is the mean of the West line of the Section and the N-S 1/4 line of Sec. 20. Established the GLO meander line by adjusting the GLO meander traverse found in the original 1845 notes, using the compass rule, and closing upon the reestablished meander corners on the north line of Sec. 20 (see Houghton County Remonumentation survey drawing of Sec. 20 dated 8/12/2012 by Crampton Surveying). The position for the corner is 418.13' north of 1/16 cor. #8.

AMC - Established the W1/16 line as described above. The direction of the partition line from the SMC north to the current shore of Little Rice Lake was determined by the proportionate shoreline method, as described on a survey drawing by the undersigned dated May 6, 2013, on file at the Michigan Dept. of Natural Resources Baraga Operations Service Center. The partition line is an extension of the W1/16 line and it intersects the shore of Little Rice Lake 1065.9' north of 1/16 cor. #8. Established a Witness Corner to the AMC position, described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(SMC) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
14" W.Pine N15°E 13.05' mrkd "SMC BT"  
4" B.Spruce S78°E 17.9' do  
5" B.Spruce S78°W 9.3' do  
6" W.Pine N53°W 6.4' do  
Set sq'd cedar post adjacent.  
E=7903580.412 N=263893.811

(AMC) Set 1"IDx32" I.pipe with 4" alum. MDNR cap  
55' south of the position for the corner and  
1010.93' north of 1/16 cor. #8 for a Witness cor.  
Set measuring nail with MDNR tag in the side of:  
4" W.Pine N02°E 9.4' mrkd "WC BT"  
4" R.Pine N62°E 3.45' do  
4" Male S19°E 9.4' do  
7" R.Pine N85°W 10.7' do  
Set sq'd cedar post adjacent.  
E=7903577.770 N=264074.475

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).

Coord. Ref.=NGS PID DL5985: N= 259878.551 m. E= 7882233.252 m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 05/07/2013

For the Michigan Department of Natural Resources, Forest Resources Division

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 7, 1971

