

SURVEY & REMONUMENTATION

APR 27 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
Iron
(County)

Located In: _____ Corner Code # _____

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey Section 8 | T <u>42N</u> R <u>32W</u> | <u>C-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

95 JAN 17 AM 8:42
L.C. RECORDS L.C.P. 332

Robert J. Stiles
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
Section corner common to Section 5, 6, 7 and 8, T42N, R32W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John R. Garske, in a field survey on October 18, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by J.B. Seal on 9/24/1849. Set sugar post from which a 24" elm - S75°W, 35 links and 24" sugar - N77°E, 15 links.

Survey by Michigan Department of Natural Resources surveyor, Arthur O. Enger, RLS 13581, on May 25, 1972. Found a 1" I.D. iron pipe flush with ground; 7" R. oak - S57°E, 11.6 feet; 7" sugar - N63°W, 13.5 feet; 6" sugar - S70°W, 10.6 feet.

1976 - MDOT R/W plans show corner position from centerline of US-2.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1" I.D. as noted above. Arthur O. Enger states in his notes that the iron pipe is located at old fence corner and checks with physical feature calls in the original government notes which I was able to confirm.

County Record Research and field search forms on file with County Representatives offices.

PEER GROUP APPROVED

Iron County
County Representative

AP. 12-15-94


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a standard county monument atop the found 1" iron pipe. A 3 1/4" aluminum cap is stamped: County Remonumentation, T42N, R32W; S-5; S-6; S-7; S-8; 1994; RLS 28410. I established the following bearing trees and reference objects: 6" maple - N57°E, 16.61 feet; 5" maple - S05°W, 8.56 feet; 10" maple - S68°W, 10.88 feet; 11" twin maple - N46°W, 31.33 feet; 6" steel rail w/sign - North - 1.0 foot.

Signed by John R Garske

Date 12/12/94

Surveyor's Michigan License No. 28410



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER

6 PAGE 332

Fed No. E-5