

RF

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>34W</u>	<u>K-4.5 (009)</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:34
L.C. Records: L. 8, P. 136
Richard J. Pisoni
REGISTER

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

North Meander Corner to Sections 11 and 12, T42N, R34W

I, Gary L. Pisoni, in a field survey on Nov. 20, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on October 7, 1851 by Guy H. Carleton, U.S. Deputy Surveyor.

Original Corner: Wood Post

Original Bearing Tree:

Aspen 10" N 85° E 38 lks (25.08 feet)

In 1988, Gary L. Pisoni, RLS, restored the corner position by setting a rebar pin on the South shore of Chicagon Lake by using an old fence line which runs North and South, which has been used as the Section line between Sections 11 and 12.

PEER GROUP APPROVED

Iron County Rep. 12-21-99

COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Found the above described corner position located on the fence line.


I accept the rebar pin as the best available evidence for restoring the corner position.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, set a 3" diameter aluminum cap over the top of the existing rebar pin and stamped as follows: Iron County Remonumentation, T42N, R34W, M.C., S-11, S-12, 1999, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

Red Maple	12"	N 68° E	25.32 feet
Cedar	6"	S 77° E	8.31 feet
Cedar	8"	S 05° E	37.35 feet
Cedar	8"	S 65° W	15.54 feet
Steel sign post		South	19.25 feet



99-136
Signed by *Gary L. Pisoni* Date 12.28.99

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

LIBER

8 PAGE 136