

SURVEY & REMONUMENTATION

FEB 21 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COMMENCING YEAR 2000
RECEIVED FOR RECORD
IRON COUNTY, MICHIGAN

For corners in

Iron
(County)

Located In:

Corner Code #

1. Public Land Survey

T 43N R 31W

✓ C.D-13w (011)

T 42N R 31W

C.D-1w (001)

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

00 DEC 22 PM 3: 27
J. C. Regan: L. 8, P. 323
Eileen L. Pisoni
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

West Meander Corner to Section 32, T43N, R31W

West Meander Corner to Section 5, T42N, R31W

I, Gary L. Pisoni, in a field survey on November 28, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on July 30, 1846 by John Burt, U.S. Deputy Surveyor.

Original Corner; Wood Post

Original Bearing Trees:

Yellow Birch 10" S 72° W 8 links (5.28 feet)
White Ash 9" N 42° W 22 links (14.52 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Corner located on the West bank of the Michigamme River and is 13' from waters edge.

Restored the corner position by single proportionate measurement and set a witness corner meander corner on line between the Southwest Section corner and the South quarter corner of Section 32.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, set a 5/8" diameter by 30" long rebar pin with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T43N, R31W, W.C.M.C., S- 32, S-5, T42N, N 89° 46' 14"E, 36.52 feet, 2000, RLS 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Balsam	8"	N 36° W	13.14 feet
Balsam	8"	N 63° E	3.24 feet
Red Pine	4"	S 28° E	13.53 feet
Sugar Maple	8"	S 31° W	26.00 feet
Steel sign post		S 68° W	0.65 feet


00-091

Signed by Gary L. Pisoni

Date 12-19-2000

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
H.D. REVISED MAY 14, 1975
27457 REVISED JAN. 1983
REGISTERED LAND SURVEYOR, 1995



LIBER

8 PAGE 323