

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 4 T 43N R 32W	16 (GCDB 360600)
	S 4 T 43N R 32W	9 (GCDB 360640)
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, Stephan J. Szyszkoski, in a field survey on 10/27/14 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(16-Sec. 4) East 1/16 corner between Sections 4 and 9. 1988 - Established by K.L.Sackett RLS midway and on line between Quarter and Section corners. Set 1"IDx36" I.P. with plastic cap. 7" Balsam S70°E 36.4', 5" Balsam N09°W 12.4', 8" Balsam N82°W 19.4', 8" Aspen S63°W 1.0'.

(9-Sec. 4) Center-East 1/16 corner, Section 4. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(16-Sec. 4) Recovered the 1988 monument in good condition and at record bearing and distance from the 1988 witnesses. Due to a calculation error made by Mr. Sackett prior to the monumentation of this corner, the monument was set approx. 91' east of the position intended in 1988. I did not accept the position of the monument and I destroyed the 1988 corner position. Established the position for the corner midway and on the Section line between Section corner 1315.87' east and Quarter corner 1315.87' west.

(9-Sec. 4) Established the position for the corner midway and on a straight line between Quarter corner 1316.98' east and the Center of Sec. 4 1316.98' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(16) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
6" Balsam S75°E 15.2' mrkd "1/16S BT"  
7" Balsam S26°E 13.8' do  
7" Balsam S52°W 9.35' do  
7" Balsam N19°W 2.5' do  
E= 7898780.971 N= 152176.427

(9) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
8" Sugar S44°E 5.15' mrkd "1/16S BT"  
8" Sugar S11°W 17.65' do  
8" Sugar N79°W 21.55' do  
5" Sugar N04°W 11.65' do  
Set sq'd cedar post adjacent.  
E= 7898797.876 N= 152983.867

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2011.000 datum.  
Coord. Ref.=NGS PID AA8081: N= 147176.690 m. E= 7895147.466 m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 03/05/2015

For the Michigan Department of Natural Resources, Forest Resources Division

