

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 43N R 33W	K5
	T	R
	T	R
2. Property Controlling in Section	S T	R
	S T	R
	S T	R
3. Miscellaneous Property in Sec.	S T	R
	S T	R
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 08/11/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-
established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K5) Corner common to Sections 11-12-13-14. 1983 - Corner noted by Glenn C. Van Neste PS 27464 on
LCRC Liber 6 Page 138. He reestablished L5 "by single proportion between SW and SE corners". Corner
shown on survey by Gary L Pisoni PS 27457 L.1 Page 122, no monument specified, used to reestablish
1/4 corner J5, midway between I5 and K5. 2003 - James H. Moore PS 28423 shows, on a survey
subdividing Section 11 (Coleman Engr. Co. job # 02082B), Fd. 2" pipe 2' above ground with distances
westerly 2650.88' to J5 and northerly 5340.64' to K3. Found no LCRC on record describing this
corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K5) Found a 1 7/8" O.D. iron pipe projecting approx. 3' above ground, with threaded fixture on top,
at the intersection of rock rubble walls to east and south. Found distance west to J5 = 2651.43',
north to K3 = 5342.17', and found G.C. Van Neste L5 substantially midway and on line between this pipe
and monumented M5, in accord with his 1983 survey. Found several nearby trees marked with blazes.
Found nearby American Can metal location poster on dead and down tree. Accepted the pipe as the best
available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K5) Found 1 7/8" OD iron pipe with fitting.
10" Maple N44E 15.3' fd. duplex nail/washer
Set measuring nail with MDNR tag in the side of:
11" Maple S33E 15.9' old blazes
8" Sugar in clump S76W 6.5' old blazes
5" Maple in clump N54W 40.6' mrkd "S11 NBT"
Sq'd cedar post adjacent
Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 09/21/2011

For the Michigan Department of Natural Resources, Forest Management Division