

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 43N R 33W	J5
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 12 T 43N R 33W	5
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 5 08/10/2011 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J5) Quarter corner common to Sections 11 and 14. 1987 - Gary L. Pisoni PS 27457 reestablished the
corner midway and on a straight line between Section corners 2651.44' east and west. Set 5/8"x32"
rebar. 2003 - Accepted by J.H.Moore PS 28423 for controlling the subdivision of Section 11 (Coleman
Engr. Co. job #02082B). Mr. Moore's dimensions east and west verify the position of the monument.

(5-Sec. 12) North 1/16 corner of Section 12. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J5) Found a 5/8" rebar with plastic cap "Pisoni RLS 27457", in good condition, 2651.43' west of
Section corner K5, with nearby 10" Balsam NBT with overgrown blazes. Accepted the monument as a
careful and faithful reestablishment of the position of the original corner.

(5-Sec. 12) Established the corner at the intersection of the N-S 1/4 line of Section 12 with the
North 1/16 line, being a line originating at 1/16 corner #3 having a direction parallel with the
north line of the Section between Corners K3 and L3. The 1/16 corner is thus 1335.49' south of
Quarter corner L3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J5) Fd. 5/8" capped rebar
10" Balsam N58E 11.9' fd. nail in side
Set measuring nail with MDNR tag in the side of:
4" Hemlock N46E 66.2' mrkd "1/4S NBT"
11" twin Sugar S75E 54.7' do
Pole O.H.U.P. P62-30033 S02W 107.5'
Set sq'd Cedar post adjacent.
Corner is 29' West of c/l Kuivila Rd, paved.
Bearings are magnetic.

(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
8" W.Pine N30E 20.6' mrkd "1/16S BT"
18" twin W.Pine S29E 54.1' do
5" Maple in clump S22W 44.0' do
20" W.Pine S85W 6.9' do
C/L Sheltrow Rd (gravel) N60W 28'
Set sq'd Cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 09/21/2011

For the Michigan Department of Natural Resources, Forest Management Division



16727

16725