

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____ T _____ R _____	_____
2. Property Controlling in Section	S 12 T 44N R 31W S _____ T _____ R _____ S _____ T _____ R _____	7
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 05/06/2010 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(7-Sec. 12) North 1/16 between Section 12, T44N-R31W and Section 7, T44N-R30W. 1969 - Established by
A.O.Enger RLS midway and on line between section corner 19.973 chains north and 1/4 corner 19.973
chains south. Set 1"IDx36" I.pipe with 4" aluminum cap. Aspen 6" S04W 11.5 links, Balsam 7" S79
1/2W 55.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(7-Sec. 12) Found the 1969 monument in good condition, at the proper position, and at record bearing
and distance from the 1969 witnesses, now both stump remains. Accepted the monument as a careful and
faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(7) Fd. 1"ID I.pipe with 4" alum. MI Dept.
of Conservation cap. Set measuring nail
with MDNR tag in the side of:
4" Maple N23E 48.2' mrkd "1/16S BT"
10" Balsam N65E 53.4' do
8" Maple S37W 9.6' do
6" Maple N09W 15.25' do
Sq'd Cedar post adjacent. Bearings magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 06/07/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division