

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 32 T 44N R 32W	1
	S 32 T 44N R 32W	12
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 12 10/11/2010 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(1-Sec. 32) West 1/16 corner between Sections 29 and 32. 1984 - Established by K.L.Sackett RLS midway and on line between section corner West and 1/4 corner East. Set 1"IDx32" Iron pipe with 4" alum. cap. 12" Hemlock S50E 52.0', 6" Balsam N09W 20.8'.

(12-Sec. 32) South 1/16 corner, Section 32. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 32) Recovered the 1984 monument and accessories as recorded. Determined that the 1984 position is in error, being S80W 6.3' from the intended position for the corner. Removed the 1984 monument and established the corner midway and on the Section line between Section corner 1319.31' west and Quarter corner 1319.31' east.

(12-Sec. 32) Established the corner midway and on a straight line between Quarter corner 1324.00' south and Center of Section 1324.00' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
6" Maple in clump N83E 16.3' mrkd "1/16S BT"  
6" Maple S44W 27.4' do  
15" Hemlock S46E 51.9' 1984 BT w/old blazes  
8" Balsam N12W 20.5' do  
Set sq'd cedar post adjacent  
Bearings are magnetic.

(12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
7" Hemlock N37E 42.0' mrkd "1/16S BT"  
13" W.Pine S82E 22.75' do  
4" double Y.Birch S73W 8.3' do  
12" double Oak N56W 26.2' do  
Set sq'd cedar post adjacent.  
Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 11/04/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

