

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 31W T R T R	E9 (GCDB 300300)
2. Property Controlling in Section	S 30 T 45N R 31W S T R S T R	14 (GCDB 200220)
3. Miscellaneous Property in Sec.	S T R S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on E9 07/06/15
14 06/30/15 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(14-Sec. 30) South 1/16 corner between Sections 29 and 30. Not previously monumented.

(E9) Corner common to Sections 20-21-28-29. 1849 - Established by John Burt, Deputy Surveyor. Set
Cedar post. Y.Birch 10" S74°E 54 links, Y.Birch 10" N17°W 53 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(14-Sec. 30) Established the position for the corner midway and on the Section line between Quarter
corner 1317.25' north and Section corner 1317.25' south. From the position thus established, I
found a 2"ID I.pipe projecting 4.8' a.g., a land-owner's approximate position, 20.1' north and 27.3'
east.

(E9) The original post and accessories were not recovered. Found no evidence of the position of the
original corner on the ground. Reestablished the position for the corner by double proportionate
measurement to the original record between corners C9 5248.39' west (79.66 chains R), G9 5269.49'
east (79.98 chains R), E7 5242.25' north (80.00 chains R), and E13 10484.25' south (160.00 chains
R).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(14) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
4" Sugar N18°W 32.0' mrkd "1/16S BT"
6" Sugar N67°E 6.3' do
7" Sugar S24°E 19.85' do
3" Ironwood S55°W 20.15' do
Set sq'd cedar post adjacent.
E= 7905839.498 N= 165354.622

(E9) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
3" Poplar N09°E 25.7' mrkd "S21 NBT"
4" Balsam S87°E 16.85' "S28 NBT"
12" Spruce S10°E 27.8' "S28 NBT"
5" Balsam S72°W 9.75' "S29 NBT"
Set sq'd cedar post adjacent.
E= 7907458.080 N= 166522.549

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum.
Coord. Ref.=NGS PID AA8081: N= 147176.690 m. E= 7895147.466 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 08/04/2015

For the Michigan Department of Natural Resources, Forest Resources Division

