

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron Located In: Corner Code #
1. Public Land Survey T 45N R 31W C11
2. Property Controlling in Section S T R (GCDB 200140)
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

Table with 13 rows and 13 columns (A-M) for Register of Deeds Stamp & File Number.

I, Stephan J. Szyszkoski, in a field survey on 06/15/15 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C11) Corner common to Sections 29-30-31-32. 1849 - Established by John Burt, Deputy Surveyor. Set Cedar post. Spruce 8" N84°W 33 links, Spruce 14" S38°E 36 links. Found no subsequent record.

(C12) Quarter corner common to Sections 31-32. 1849 - Established by John Burt, Deputy Surveyor, midway and on the Section line between Section corners 40.00 chains north and south. Set Cedar post. Cedar 8" N32°W 18 links, Cedar 7" S53°E 25 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C11) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the position for the corner by double proportionate measurement to the original record between corners B11 2636.27' west (40.00 chains R), G11 10559.54' east (160.22 chains R), C9 5269.01' north (80.00 chains R), and C13 5269.01' south (80.00 chains R).

(C12) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner midway and on the Section line between Section corners 2634.50' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C11) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
9" B.Spruce N50°W 22.75' mrkd "S30 NBT"
9" B.Spruce N30°E 8.1' "S29 NBT"
10" B.Spruce S84°E 18.05' "S32 NBT"
9" B.Spruce S42°E 15.6' "S32 NBT"
A 2" IDx6' long iron pipe stands adjacent.
E= 7905832.981 N= 164953.243

(C12) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
6" B.Ash N51°W 2.2' mrkd "1/4S NBT"
5" B.Ash N83°E 2.7' do
9" Balsam S21°E 18.55' do
6" Tamarack S37°W 23.4' do
Set sq'd cedar post adjacent.
E= 7905818.674 N= 164150.508

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 data.
Coord. Ref.=NGS PID AA8081: N= 147176.690 m. E= 7895147.466 m.

Signed by [Signature]
Surveyor's Michigan License No. 33986

Date 08/04/2015

For the Michigan Department of Natural Resources, Forest Resources Division

