

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____ T 45N R 31W	M3
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____ S _____ T _____ R _____	(GCDB 700600)
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____ S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on A3 05/11/16 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 1-12 T45N-R31W and Sections 6-7 T45N-R30W. 1969 - Reestablished by A.O.Enger RLS by proportionate measurement on line between corners 80.07 chains south and 81.923 chains north. Set 1"IDx36" I.pipe with 4" alum. cap. B.Spruce 6" S59°W 11 links, B.Spruce 6" S72°E 15.5 links, B.Spruce 8" N21°E 40 links, B.Spruce 5" N31°W 18.5 links. I note that the proportion used by Mr. Enger is not correct. Using the GLO record 80.00 chains south and 81.65 ch. north, the proportion should have been 80.17 ch. south (measured) and 81.823 ch. north (measured). An examination of the 1969 calculation sheet indicates that Mr. Enger erroneously used 161.85 chains as the GLO record from M5 to M1, rather than the correct 161.65 chains.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The 1969 monument was found disturbed by a windthrown tree. Reestablished the 1969 position at record bearing and distance from the two remaining 1969 NBTs: B.Spruce S72°E 15.5 links in good condition, and B.Spruce N31°W 18.5 links, now a rotted stump. Found the distance from this position to M1 to be 81.871 ch. (5403.46'). This position is only 3.2' south of that which Mr. Enger would have monumented had he calculated the position using the correct GLO record values. The position having been monumented for 47 years and the positions of least 6 other monumented corners influenced by Mr. Enger's relatively minor calculation error, I accept the 1969 position as a faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:



Set 1"IDx28" I.pipe with 2" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
8" Spruce S73°E 10.6' old blazes (1969 NBT)  
5" Tamarack S23°W 38.6' mrkd "S12 NBT"  
5" R.Pine S88°W 13.85' do  
3" Spruce N26°E 8.45' "S6 NBT"  
Set sq'd cedar post adjacent.  
E= 7913983.35 N= 171221.52

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum.  
Coord. Ref.=NGS PID AA8080: N= 192972.689 m. E= 7925456.741 m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 05/19/2016

For the Michigan Department of Natural Resources, Forest Resources Division