

# SURVEY & REMONUMENTATION

FORM NO. 985-A



Stock No. 26273

MAR 19 1997

## COMMISSION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron

(County)

Located In:

Corner Code #

1. Public Land Survey

T 46N R 34W

D.E-13B (001)

~~T 45N R 34W~~

~~D.E-1B (002)~~

T R

T R

2. Property Controlling  
in Section

S T

T R

S T

T R

3. Miscellaneous  
Property in Sec.

S T

T R

S T

T R

4. Lot No. , Recorded Plat

5. Private Claims

East Witness Corner

Meander Corner between S.32, T46N R34W  
S.5, T45N R34W

I, Gary L. Pisoni, in a field survey on October 18, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Burt, U.S. Deputy Surveyor on September 18, 1846.

Original corner: 7" Spruce Corner tree

Original bearing trees:

Hemlock

14"

N 57° E

28 links (18.48 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence found.

Set Witness Corner Meander Corner on East shore of Porter Lake, on line between the North Quarter corner and Northeast Section corner of Section 5, T45N R34W.

Corner Record Research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 5/8" diameter by 30" rebar pin, 2" above ground surface and and 12 feet from waters edge with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T46N, R34W, W.C., M.C., S-32, S-5, T45N, 1996, RLS-27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Red Maple	7"	S 70° E	8.35 feet
Cedar	6"	S 20° E	45.70 feet
White Pine	20"	N 67° W	6.22 feet
Steel Sign Post	6'	N 52° E	0.85 feet

#96-14

Signed by Gary L. Pisoni

Date 12-10-96

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

95 DEC 23 AM 9:00

L.C. Records L. 7, P. 36


*Gary L. Pisoni*  
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

PEER GROUP APPROVED

*Gary L. Pisoni* 12-11-96  
COUNTY REPRESENTATIVE



L. 7 P. 36