

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 33W	E10 (GCDB 300240)
2. Property Controlling in Section	S 32 T 46N R 33W	7 (GCDB 300160)
3. Miscellaneous Property in Sec.	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on E10 06/02/15 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E10) Quarter corner common to Sections 28 and 29. 1985 - Reestablished by K.L.Sackett RLS midway  
and on line between Section corners. Set 1"IDx32" I.pipe with 4" alum. cap. 4" Spruce S40°E 16.2',  
10" Spruce N39°E 6.7', 10" Spruce N62°W 17.3'.

(7-Sec. 32) North 1/16 corner between Sections 32 and 33. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E10) The 1985 monument was recovered in good condition and at record bearing and distance from all  
three 1985 accessories, now all dead and down. The monument is substantially at the midway position  
of record and I accept same as a careful and faithful reestablishment of the position of the  
original corner.

(7-Sec. 32) Established the position for the corner midway and on the Section line between Section  
corner 1322.13' north and Quarter corner 1322.13' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E10) Found 1"ID I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
3" Poplar N07°E 7.05' mrkd "1/4S NBT"  
4" Elm S58°E 18.6' do  
6" Balsam S34°W 12.05' do  
3" Poplar N60°W 15.1' do  
Set sq'd cedar post adjacent.  
E= 7888425.860 N= 175709.792

(7) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
4" Tamarack N29°E 2.0' mrkd "1/16S BT"  
8" Tamarack S16°E 18.4' do  
4" Tamarack S29°W 13.55' do  
4" B.Spruce S89°W 6.40' do  
Set sq'd cedar post adjacent.  
E= 7888396.139 N= 174504.151

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum  
Coord. Ref.=NGS PID RL0476: N= 196482.411 m. E= 7879234.516 m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 08/06/2015

For the Michigan Department of Natural Resources, Forest Resources Division

