

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 34W T _____ R _____ T _____ R _____	MC N. of I8 (GCDB 500366)
2. Property Controlling in Section	S 22 T 46N R 34W S _____ T _____ R _____ S _____ T _____ R _____	5 (GCDB 440360)
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

100

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on MC 01/21/15 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(5-Sec. 22) Center-North 1/16 corner, Section 22. Not previously monumented.

(MC N. of I8) Meander corner on the south shore of Spring Lake between Sections 22 and 23. 1852 - Established by Z.B.Searles, Deputy, 66.05 chains north of Section corner I9 and 25.93 chains north of 1/4 corner I8 and on the Section line defined by those two corners. Set post. Tamarack 4" S40°E 50 links, Tamarack 3" S20°W 28 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(5-Sec. 22) Established the position for the corner midway and on a straight line between Quarter corner H7 1323.80' north and the intersection of 1/4 lines of Section 22 1323.80' south.

(MC) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner on the line I9 to I8, produced north, and at record distance north of I8 proportioned to the ratio of the original record and observed distance between I8 and I9 (R=40.12 ch. M=2644.29'), specifically 1709.03' north of I8, viz: 25.93 ch R/40.12 ch R * 2644.29' M = 1709.03'. The position for the corner is wet and cannot be monumented. Established a WITNESS CORNER on the Section line 50.00' south of the position for the Meander Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(5) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
4" Sugar N16°E 17.65' mrkd "1/16S BT"
8" Sugar S59°E 2.8' do
6" Sugar S02°W 24.75' do
11" Y.Birch S59°W 26.45' do
Set sq'd cedar post adjacent.
E= 7881232.321 N= 177864.551

(WCMC) Set 1"IDx28" I.pipe with 2" alum. MDNR cap stamped "M.C. 50.0' ↑ [i.e., north] 22|23". Set measuring nail with MDNR tag in the side of:
4" Tamarack N08°E 22.75' mrkd "WC BT"
6" Tamarack N76°E 9.65' do
4" B.Spruce S22°E 12.0' do
4" B.Spruce S81°W 28.05' do
Set sq'd cedar post adjacent.
E= 7882036.543 N= 177959.215 (the W.C.M.C.)

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum.
Coord. Ref.=NGS PID RL0476: N= 196482.411 m. E= 7879234.516 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 05/19/2015

For the Michigan Department of Natural Resources, Forest Resources Division

