

# SURVEY & REMONUMENTATION

FORM NO. 985-A



Stock No. 26273

MAR 19 1997

## COMMISSION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

95 DEC 23 AM 9:00

L.C. Records L. 7, P. 35

*Gary L. Pisoni*  
REGISTERED LAND SURVEYOR

For corners in

Iron  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 46N R 34W

E-13

T 45N R 34W

E-1

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Section Corner 32 & 33, T46N R34W  
5 & 4, T45N R34W

I, Gary L. Pisoni, in a field survey on October 18, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor on September 18, 1846.

Original corner: Cedar Post

Original bearing trees:

Hemlock 14" N 07° E 17 links (11.22 feet)

Fir 8" N 73° W 64 links (42.24 feet)

On September 19, 1985, Keith L. Sackett R.L.S., M.D.N.R., set a 1" I.D. by 32" iron pipe with 4" aluminum cap from a found wood post. No original corner evidence was found.

Recorded in Land Corner Certificate L. 6, Page 111.

1985 bearing trees:

Sugar Maple 5" N 01° W 9.6 feet

Sugar Maple 7" N 79° E 18.5 feet

Sugar Maple 10" N 47° W 16.8 feet

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found monument and bearing trees as described above.

Sugar Maple 7" N 05° E 9.77 feet

Sugar Maple 9" N 77° E 18.67 feet

Sugar Maple 11" S 48° W 17.29 feet

Wood Post 4" x 4" North 0.40 feet

Corner Record Research on file with County Representative.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described aluminum cap monument, I established the following new blazed and scribed bearing tree: (all measurements taken to a nail in side of tree)


Yellow Birch 11" S 58° E 16.38 feet

Steel Sign Post 6' WEST 1.00 feet

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

PEER GROUP APPROVED

*Iron Gary L. Pisoni 12-1-96*  
COUNTY REPRESENTATIVE



36-13

igned by *Gary L. Pisoni*

Date 12-10-96

urveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

REVISED OCT., 1995

L. 7 P. 35