

**SURVEY &  
REMONUMENTATION**

JAN 19 1999

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>34W</u>	<u>C D-11e</u>
	T _____ R _____	<u># 003</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

98 DEC 28 AM 11:28  
L.C. Records: L. 7, P. 331

*Gary L. Pisoni*  
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

East Meander Corner Sections 29 and 32, T46N R34W

I, Gary L. Pisoni, in a field survey on June 1, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Z.B. Searls, U.S. Deputy Surveyor on July 9, 1852.

Original corner: Wood Post  
Original bearing trees:

Spruce	12"	N 04°E	10 links (6.60 feet)
Cedar	8"	S 23°E	8 links (5.28 feet)

PEER GROUP APPROVED  
Gary L. Pisoni 12-18-98  
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner restored at record bearing and distance from an original bearing tree. No evidence of Spruce bearing tree found. Found the cedar bearing tree which is a 14" diameter stub approximately 12' tall with scribing and notch visible

Corner Record Research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


At the corner position, set a 3/4" diameter aluminum rod monument, 3 feet long with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T46N, R34W, M.C., S-29, S-32, 1998, RLS 27457 from which I established the following new blazed and scribed bearing trees: (All measurements taken to a nail in side of tree)

Red Maple	10"	S 58°E	26.70 feet
Balsam	5"	S 27°W	23.00 feet
Red Maple	8"	N 47°W	13.58 feet
Iron Bar	1" diameter	N 58°E	4.41 feet
Steel sign post		North	0.80 feet

#98-159  
Signed by Gary L. Pisoni  
Surveyor's Michigan License No. 27457

Date 12-21-98

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN 1983  
REVISED OCT., 1995



L. 7 P. 331