

\$7.00
\$2.00

SEP 18 1955

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>12W</u>	<u>J-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
RECEIVED FOR RECORD
85 AUG 28 AM 10:53
8638
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on April 7 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-3	1831	G.L.O. Notes	Mullett	Set Post
	1962	Wit. Map	K.C. Surveyor	Iron & Stone
	1975	L.C.R.C. #896	Exxel Engineering	Found 1/2" Iron
	1977	L.C.R.C. #1053	M & B	Found 3/4" Iron
	1980	L.C.R.C. #1519	Exxel Engineering	Found 3/4" Iron & Stones/Set K.C. Monument
	1990	L.C.R.C. #5692	Chris Marschall	K.C. Monument
	1991	L.C.R.C. #6338	Chris Marschall	K.C. Monument

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Exxel Engineering on 11/25/80 and was recorded per L.C.R.C. #1519.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-3 Found standard Kent County Monument 5.0' South of the C/L of 68th Street running E-W per L.C.R.C.'s #5692 and #6338 as set by Exxel Engineering in place of a 3/4" iron and stones they found which checked K.C. Surveyor's Wit. Map (1962).

L.C.R.C. #5692

L.C.R.C. #6338


Nail & Remon. tag in W side 22" Oak, N 10° E, 167.79'
Nail & Remon. tag in E side 18" Cherry 3' high, S 02° E, 140.78'
Nail & Remon. tag on SW side 14" Cherry 3' high, S 55° E, 185.19'
"X" cut in top of E end 36" conc. culvert, S 62° W, 134.24'
Top centerline fire hydrant, N 63° W, 200.88'
SW corner catch basin rim, N 65° E, 39.41'
Centerline pavement, North 5' ±
Centerline "X" Sunfield Drive & 68th St. West 155'±

Nail & Remon tag in W side 22" Oak N 10 E 167.79'
Nail & Remon tag in E side 18" Cherry 3' high, S 02 E 140.78'
Nail & Remon tag in SW side 14" Cherry 3' high, S 55 E 185.19'
"X" cut in top of E end 36" conc. culvert, S 62 W 134.24'
Top centerline fire hydrant, N 63 W 200.88'
SW corner catch basin rim, N 65 E 39.41'
Centerline pavement North 5 more or less
Centerline "X" Sunfield Drive & 68th St. West 155 more or less

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-3 Standard Kent County Monument
Nail & K.C. remon. tag on W side 22" Oak N 10° E 167.79'
Nail & K.C. remon. tag on E side 18" Cherry 3' high, S 02° E 140.78'
Nail & K.C. remon. tag on SW side 14" Cherry 3' high, S 55° E 185.19'
"X" cut in top of E end 36" conc. culvert, S 62° W 134.24'
Top centerline fire hydrant, N 63° W 200.88'
SW corner catch basin rim, N 65° E 39.41'
Centerline pavement North 5 more or less
Centerline "X" Sunfield Drive & 68th St. West 155 more or less



Signed by Randy J. Kolehouse Date 8/21/95

Surveyor's Michigan License No. 25854