

SURVEY & REMONUMENTATION

MAY 09 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Kent

Located In:

SOLON TOWNSHIP
Corner Code 11

1. Public Land Survey

T 10N R 11W

South witness
monument to F-1

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

4. Lot No

Recorded Plat

5. Private Claims

Wallace E. Glaza in a field survey on July 22, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration

No previous history.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

South witness monument to F-1, Section 4, T10N, R11W, Solon Township, Kent County, Michigan.


Set standard 4" x 30" Harrison Monument 7'± South and 10' East of waters edge of Gilbert Lake on a straight line between the North 1/4 corner (mathematical) and the center of Section.

Witness corner is 2791.35' North of center of Section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

South witness monument to F-1 (4" x 30" standard Harrison Monument)

- 1) Nail and tag in N side 30" Maple N70°E 9.44'
- 2) Nail and tag in SE side 14" Pine S50°W 14.34'
- 3) Nail and tag in E side 28" Pine S20°W 17.43'
- 4) Nail and tag in E side 18" Beech S30°W 45.42'
- 5) North-South fence East 1.5'±



Signed by

Wallace E. Glaza
Glaza and Associates, Inc.

Date

8-9-93

Surveyor's Michigan License No.

31592