

SURVEY &
REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Keweenaw

(County)

Located In:

Corner Code ##

1. Public Land Survey

T 57N R 32W

A-4

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

REGISTER'S OFFICE

County of Keweenaw

SS

Received for Record, the 20th

day of January A.D. 1995

at 10:30 o'clock A.M., and Recorded

in Liber 1 of LCR

on page 131

Marilyn W. Winkler
Register of Deeds

Register of Deeds Stamp & File Number

I, John I. Haataja, in a field survey on November 21, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-4 1/4 Cor. Between Sec. 7, T57N-R32W and
Sec. 12, T57N-R33W.

Orig. Notes set wood post

Maple 8" S 68° E 14 lks.

Hemlock 32" N 52° W 42 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-4 1/4 Cor. Between Sec. 7, T57N-R32W and
Sec. 12, T57N-R33W.

No trace of original corner found.

Re-established corner by single proportion
between adjacent section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4 1/4 Cor. Between Sec. 7, T57N-R32W and
Sec. 12, T57N-R33W.

Set a 1" iron pipe with brass cap and is a
careful and faithful re-establishment of
the position of the original corner.


8" Balsam S 48° E 13.31'

10" W. Birch N 47° W 1.12'

12" W. Birch S 30° W 27.97'

12" Maple N 4° E 35.43'

Ratified by Peer Group
In accordance with P.A. 345
Co. Rep. *James M. Tindall*
Date 11/16/94



Signed by *John I. Haataja*

Date December 28, 1994

Surveyor's Michigan License No. 19833