

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. PA 1970

For Corner in:

Lake Located In Corner Code #
(County)

1. Public Land Survey T 18N R 12W I-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

4. Lot No: Recorded Plat:
5. Private Claims:

I, Craig W. McVean, in a field survey on June 16, 2014 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

Table with 13 rows and 13 columns (A-M). A dot is marked at the intersection of row 1 and column H.

A. Description of original monument and accessories and/or subsequent restoration:

I-1 - 1838 - GLO - J. Hodgson - N bdy 46 links East of post. Set post at intersection.
1) 7" Maple S37°W 22 L. 2) 9" W Oak S59°E 33 L.:
- 1973 - LCRC - L.02, p.149 - C. F. Roser (PS #12028) Established per Standard BLM instructions. Set DNR Monument.
3) 5" Maple S82°W 7.2'; 4) 8" R. Oak S47°E 9.7'; 5) Cor. Sec. 34 & 35 - West 30.23'
- 1999 - LCRC - L.4, p.198 - R. L. Wetherell (PS #24624) Fd DNR monument 1 1/2" pipe w/alum cap ± 25' West of old trail road, witnesses #1, #2, & #4 gone, #5 badly bent, #3 fd stump. Accepted DNR monument as a substantial marker for the corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.
6) N18°W 33.02' to set 60d spike in W side 13" R Oak; 7) N23°E 30.92' to set 60d spike in W side 14" R Oak; 8) N60°E 67.15' to set 60d spike in N side 15" W Oak; 9) S39°E 54.06' to set 60d spike in SW side 4" W Oak.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-1 - Closing corner common to Sections 2 & 3, T18N, R12W - Fd 1" x 36" galv. iron pipe (Dept. of Conservation (DOC) cap broken off) per Roser & Wetherell. No GLO evidence found. CL of trail road is 26' East. Condition of witnesses as follows: #1, 2 - are gone; #3 - 2nd regrowth from stump; #4 - Stp. hole; #5 - Found beat and broken DOC Mon.; #6, 7, 8 & 9 - are OK. Broken DOC monument accepted as a careful & faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 - Replaced broken DOC monument with stamped 4" DNR alum. cap on 1" x 2.8' long galv. iron pipe. Set Blue Composite Post 1' South.

N20°W 33.01' to fd. 60d nail in W side 19" Oak (#6)
N14°E 30.87' to fd. 60d nail in W side 22" Oak (#7)
N54°E 67.14' to fd. 60d nail in NW side 16" W Oak (#8)
S39°E 54.02' to fd. 60d nail in SW side 6" W Oak (#9)
West 30.23' to DNR mon. (replaced bent DOC mon.) at 'I13', T19N, R12W (#5)



Signed by: [Signature]
Surveyor's Michigan License No.: 39088

Date: 8/12/2014