

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:

Lake  
(County)

Located In

Corner Code #

1. Public Land Survey T 19N R 11W H6  
T R
2. Property Controlling in Section S T R  
S T R
3. Miscellaneous Property in Section S T R  
S T R

4. Lot No: Recorded Plat:

5. Private Claims:

I, Joshua R. Davidson, in a field survey on June 27, 2012 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**



RECEIVED  
05/05/2014 3:55:21 PM  
LAKE COUNTY, MICHIGAN  
SHELLY MYERS, CLERK/REGISTER/CFO

RECORDED  
05/05/2014 3:56:18 PM  
LAKE COUNTY, MI  
SHELLY MYERS, REGISTER OF DEEDS

RECEIPT# 5795, STATION 1  
\$14.00 LAND CORNER



Liber C8

Page 20

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7		8			9		10		11		12	
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

**H6 – Center of section 15, T19N, R11W**

2010 – Certificate of Survey – file #12491-10  
– P. Johnson, PS #47956 – Found 1/2" rerod #47956.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**H6 – Center of section 15, T19N, R11W**

Found 1/2" X 18" rebar and cap #47656 at fence corner. Fences to South and East. Calculated intersection of 1/4 lines is 0.33' South and 0.44' West. Accepted 1/2" by 18" rebar and cap #47656 as the best available evidence of the position of the corner and replaced it with a stamped 2" DNR aluminum cap on a 5/8" X 34" rebar.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**H6 – Stamped 2" DNR Aluminum Cap on 5/8" X 34" rebar.**

N20°E 31.89' to set nail & tag in W. side 6" W. Pine  
N68°E 17.10' to set nail & tag in S. side 14" R. Maple in clump of 5  
S65°W 7.35' to set nail & tag in S. side 5" Oak  
N63°W 7.27' to set nail & tag in N. side 4" Oak

Set Blue carsonite post with location tag 1' Northwest.

Signed by:

*Joshua R. Davidson*

Date:

*May 5, 2014*

Surveyor's Michigan License No.:

46659

