

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>19</u> N. <u>12</u> W. <u>12</u>	J-9; M-12
2. PROPERTY CONTROLLING IN SECTION <u>36</u>	T. <u>19</u> N. <u>12</u> W. <u>14</u>	14
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 6-7 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- J-9 Restored corner at remains of fence corner. Fence remains N & E, which fit old N.B.T. by G. Johnson survey of record.
- M-12 Reestablished corner per standard B.L.M. instructions.
- 14 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9	M-12	14
Set DNR Mon & Cedar Gd.Post	Set DNR Monument	Set 1"x36" pipe, buried, on W edge of N-S Sand Rd.
8" Ash N16E 30.2	12" 2-clump Cherry S70W 54.2'	9" B.Oak N46W 74.5
21" Sugar Maple S61E 22.7	NW leg stl tower	16" B.Oak S57W 68.8
	#3938 S32E 61.5' SW leg steel tower	
	Set Ced.Post w/loc	#3940 N13E 166.2
	Tag Due W 33'	Set Ced Post w/loc
	Ctr. N-S Sand Road Due E 21'±	tab Due W 33'

SIGNED BY

Carl F. Roser

DATE

7-16-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY


CHIEF OF SURVEY PARTY

DATE

APPROVED AND SIGNED BY

MICHIGAN REGISTERED LAND SURVEYOR

DATE



SURVEYOR'S MICHIGAN REGISTRATION NO. _____