

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

Lake (County)	Located In	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>12W</u>	<u>C13</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on April 11, 2011 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|--|
| <p><u>C13</u> – 1837 – GLO – J. Hodgson – Set post corner</p> <ul style="list-style-type: none"> 1) Pine 14" N27°W 45 2) Pine 12" N12°E 60 <p>- 1935 – By West – F. Jones Book</p> <ul style="list-style-type: none"> 3) B. Oak 9" N50°W 37'7" 4) B. Oak 9" S35½°W 27'8" <p>- 1972 – LCRC – L. 2, p. 118 and DNR Survey Projects #72-11 and #70-38. Re-established corner per Standard BLM instructions. The Northeast corner of Section 6 is 15.2' East (#5)</p> <ul style="list-style-type: none"> 6) J. Pine 7" N43°W 83.1'; 7) B. Oak 11" S63°W 65.5' | <p>- 2003 – Rec. Survey L. 5, p. 71 – P. N. Johnson –</p> <ul style="list-style-type: none"> 8) 8" B. Oak S06°W 106.98'; 9) 8" Cherry S60°E 38.43'; 10) 14" B. Oak N45°E 49.40'; 11) 6" W. Oak N50°W 64.37'. |
|--|--|

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C13 – Standard Corner Common to Section 31 & 32, T19N, R12W – Found a broken 4" Aluminum Dept. of Conservation cap on 1" iron pipe, buried 1.7' down. 12' West of centerline of N-S sand rd. on centerline of sand rd. West. No evidence of GLO, Jones, or C. F. Roser witnesses. Broken Dept. of Conservation monument accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C13 – A broken 4" Aluminum Dept. of Conservation cap on a 1" iron pipe

- S88°15'E 15.21' to found Dept. of Conservation monument "C1", T18N, R12W (#5)
- N56°W 64.50' to found nail in S. side 6" White Oak (#11)
- N26°W 68.44' to set nail and tag in SW side 7" Red Pine scribed 'XBT'
- N35°E 49.41' to found nail in SE side 15" Oak (#10)
- S78°E 39.34' to set nail & tag in S. side 10" White Pine scribed 'XBT'
- S68°E 38.35' to found 60d nail in S. side 10" Cherry (#9)
- S02°W 106.87' to found 60d nail in E. side 12" Oak (#8)



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 10/25/2011