

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 10W	C4
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 06/29/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C4) Quarter corner common to Sections 7 and 8. 1853 - Established by Geo.H.Cannon Deputy Surveyor, in a correctional survey, on the Section line between Section corners S0 deg. 28'E 40.30 chains and N0 deg. 30'W 40.49 chains. Old post. Maple 8 S67W 15.5 links, Y.Birch 10 N75E 16 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C4) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement to the 1853 record between Section corner C5 S1 deg. 00'15"E 2665.92' and Section corner C3 N1 deg. 02'15"W 2678.50' (true bearings).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C4) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" B.Spruce N64E 4.8' mrkd "1/4S NBT"
 7" Maple in clump S06E 11.3' do
 9" Birch S84W 16.4' do
 10" Maple N08W 24.7' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/26/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division