

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 10W T 46N R 11W T R S T R S T R S T R S T R	A4 same M4 corner       
2. Property Controlling in Section		
3. Miscellaneous Property in Sec.		
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 07/12/2010 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A4) Quarter corner common to Section 7 T46N-R10W and Section 12 T46N-R11W. 1841 - Established by  
W.A.Burt Deputy Surveyor on the Range line midway between Section corners 40.00 chains north and  
south. Set post. Fir 8" N40W 7 links, Hemlock 16" N59E 61 links. 1974 - Billy D. Buckler RLS  
reestablished the corner position by single proportionate measurement between Section corners 1/2  
mile north and 1/2 mile south. Set 1"IDx36" I.pipe with 4" alum. MDNR cap. 6" S.Maple N89E 16.1',  
6" S.Maple S25W 7.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A4) The original post and accessories were not recovered. Found the 1974 monument in good  
condition, substantially at the record position between Section corners, and at record bearing and  
distance from the 1974 NBTs (Maple NE is in good condition, Maple SW a rotted stump). Accepted the  
monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A4) Found 1"ID I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
10" Maple S89E 16.4' mrkd "1/4S" 1974 NBT  
5" Balsam S54E 7.3' mrkd "1/4S NBT"  
4" Maple S31W 6.65' do  
9" Maple N38W 37.0' do  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/26/2010  
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Forest Management Division