

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 10W T R T R	E12 (GCDB 300140)
2. Property Controlling in Section	S 32 T 48N R 10W S T R S T R	11 (GCDB 220120)
3. Miscellaneous Property in Sec.	S T R S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on E12 03/24/15  
11 03/26/15 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E12) Quarter corner common to Sections 32 and 33. 1853 - Established by George H. Cannon, Deputy,  
midway and on the Section line between Section corners 40.27 chains north and south. Set post.  
Balsam 11" N42°E 18 links, Beech 11" S48°W 32 links. Found no subsequent record.

(11-Sec. 32) Southwest 1/16 corner, Section 32. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E12) The original post and accessories were not recovered. Found no acceptable evidence of the  
position of the original corner on the ground. Reestablished the position for the corner on the  
Section line between Section corners 2656.47' north and south, proportionate to the original record.

(11-Sec. 32) Established the position for the corner at the intersection of straight lines  
connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E12) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
18" Hemlock S64°W 11.14' mrkd "1/4S NBT"  
15" Hemlock N15°W 6.51' do  
11" Maple N84°E 23.33' do  
10" Hemlock S37°E 29.26' do  
E= 8109469.115 N= 193228.772

(11) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
6" Maple S85°E 10.41' mrkd "SW1/16 BT"  
5" Maple S28°W 21.47' do  
5" W.Birch N52°W 6.65' do  
6" B.Spruce N02°E 19.74' do  
E= 8108265.347 N= 192796.139

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2038.0 datum.  
Coord. Ref.=NGS PID RJ0491: N= 184295.153 m. E= 8114482.997 m.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 04/28/2015

For the Michigan Department of Natural Resources, Forest Resources Division

