

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 30 T 49N R 8W	B10
	S 30 T 49N R 8W	9
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	28		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 12/15/2011 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B10) Center of Section 30. 1977 - Established and monumented by Billy D. Buckler RLS at the intersection of Quarter lines. Set 1" pipe with 4" aluminum cap. 6" Jack Pine N28E 41.1', 6" Jack Pine S60E 35.7'.

(9-Sec. 30) East 1/16 corner, Section 30. 1977 - Established and monumented by Billy D. Buckler RLS midway between Center of Section to West and Quarter corner to East. Set 1" ID I. pipe with 4" aluminum cap. 8" W. Pine S87E 26.0', 12" W. Pine S06W 10.25', 8" Spruce N54W 13.25'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B10) Found the 1977 monument in good condition and at record bearing and distance from the 1977 witnesses. The Jack Pine NE is standing dead, the Jack Pine SE is a stump. This corner is being recorded to update the accessories.

(9-Sec. 30) Found the 1977 monument in good condition and at record bearing and distance from the 1977 witnesses. The W. Pine SE and Spruce NW are now stumps. The W. Pine SW is in good condition. This corner is being recorded to update the accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B10) Fd. 1" ID I. pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
8" J. Pine S88E 50.05' mrkd "CS BT"
9" J. Pine S50E 49.05' do
8" J. Pine N57W 35.1' do
8" J. Pine S61W 38.75' do
Bearings are magnetic.

(9) Fd. 1" ID I. pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
15" W. Pine S08W 11.0' mrkd "E1/16" 1977 NBT
8" W. Pine S64E 19.35' "E1/16 BT"
8" W. Birch N72W 23.25' do
12" W. Pine N38W 21.65' do
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 03/13/2012

For the Michigan Department of Natural Resources, Forest Resources Division

