

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| <u>Luce</u> (County) | Located In: | Corner Code # |
|---------------------------------------|-------------|-----------------|
| 1. Public Land Survey | T 50N R 8W | MC bet. A11-B11 |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |
| 4. Lot No. , Recorded Plat | | |
| 5. Private Claims | | |

I, Stephan J. Szyszkoski, in a field survey on 10/08/2007 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(MC between A11-B11) Meander corner on the north line of Section 31, at the West shore of Culhane
Lake. 1958 - Remonumented in the original position by Billy D. Buckler RLS from the two original
bearing trees. Set 1.5" x30" Well point at water's edge. 11" Red Pine N64W 91.5 links, 7" Cedar
S56W 57 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(MC) Found the 1958 monument well point, laying nearly horizontally, probably pushed over by ice
movement. Found both of the 1958 bearing trees in good condition with overgrown blazes. Placed a
new monument at the position of the base of the well point and at record bearing and distance from
the 1958 witnesses. The position for the corner now falls in the water, 12' east of the current
lakeshore.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(MC) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
13" Cedar S60W 37.9' mrkd "MC" 1958 NBT
13" Cedar N44W 34.95' mrkd "MC NBT"
6" Cedar West 24.53' do
9" Cedar S40W 29.3' do
W. shore of Culhane Lake West 12'.
Bearings are magnetic.



Signed by

Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date

03/18/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

Revised May 14, 1975

Revised Jan., 1983

Revised Oct., 1995