

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 25 T 50N R 9W	9
	S 25 T 50N R 9W	12
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

01/15/2008

01/15/2008

I, Stephan J. Szyszkoski, in a field survey on _____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(9-Sec. 25) East 1/16 corner, Section 25. 1970 - Established by Billy D. Buckler RLS midway and on line between Center of Section and East 1/4 corner. Set 1" pipe with 4" aluminum cap. 10" Red Pine N41E 10.2', 14" Red Pine S12W 18.5'.

(12-Sec. 25) South 1/16 corner Section 25. 1970 - Established by Billy D. Buckler RLS midway and on line between Center of Section and South 1/4 corner. Set 1" pipe with 4" aluminum cap. 10" Red Pine S09E 11.6', 10" Jack Pine S81W 17.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(9-Sec. 25) Found the 1970 monument in good condition, at the record position, and at record bearing and distance from the Red Pine BT SW, in good condition. Accepted same as a careful and faithful establishment of the position of the corner.

(12-Sec. 25) Recovered the 1970 monument in good condition, at the record position, and at record bearing and distance from the 1970 R.Pine BT, in good condition. Accepted same as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(9) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
18" R.Pine S14W 18.95' mrkd "E1/16" 1970 BT
12" R.Pine S47W 13.95' mrkd "E1/16 BT"
10" R.Pine N16W 8.5' do
6" R.Pine N70E 26.2' do
Bearings are magnetic.

(12) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
16" R.Pine S07E 12.04' mrkd "S1/16" 1970 BT
9" R.Pine S49E 31.82' mrkd "S1/16 BT"
12" W.Pine S85E 44.35' do
16" R.Pine N12W 20.92' do
Bearings are magnetic.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Signed by

Stephan J. Szyszkoski

Date

03/18/2008

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

