

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Mackinac (County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 1E	L7
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 13 T 42N R 1E	12
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on L7 02/09/2010 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L7) Quarter corner common to Sections 13 and 24. 1845 - Established by John Mullett, Deputy
Surveyor, midway and on the Section line between Section corners 40.11 chains east and west. Set
post. W.Pine 18" N56E 14 links, Cedar 8" S58W 9 links.

(12-Sec. 13) South 1/16 corner, Section 13. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L7) The original post and accessories were not recovered. Found no evidence of the position of the
original corner on the ground. Reestablished the corner midway and on the Section line between
Section corners 2628.44' east and west.

(12-Sec. 13) Established the corner midway and on a straight line between Quarter corner 1295.64'
south and Center of Section 13 1295.64' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L7) Set 1"IDx36" I.pipe with 4" alum. MDNR cap
made firm in a mound of rock. Set measuring nail
with MDNR tag in the side of:
16" Cedar N50W 10.3' mrkd "1/4S NBT"
9" Cedar N88E 9.25' do
8" Cedar S22W 45.65' do
10" Cedar S54W 35.55' do
Bearings are magnetic.

(12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
6" W.Birch N56E 4.05' mrkd "S1/16 BT"
6" Balsam S08E 9.0' do
8" W.Birch S56W 19.85' do
6" W.Birch N24W 22.05' do
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 05/20/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division



47363

47364