

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Mackinac (County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 01W	D7
	T R	
	T R	
2. Property Controlling in Section	S 17 T 42N R 01W	D6
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 09/11/13 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D6) Center of Section 17. 1957 - Billy D. Buckler RLS established the position for the corner at
the intersection of 1/4 lines. Set 2.5"x4.5 ft. iron pipe. 13" Cedar South 9 links, 6" Cedar N55°W
39 links.

(D7) Quarter corner common to Sections 17 and 20. 1957 - Remonumented by Billy D. Buckler RLS.
1998 - Rewitnessed by Neil E. Hill PS and reviewed and approved by the Mackinac Co. Peer Group and
recorded in Liber E of LCR, Page 287. 1" pipe with 4" brass DNR cap. 24" W.Pine S80°W 24.92', 18"
W.Pine N15°W 29.40', 6" W.Pine S85°E 29.95', 14" Spruce N25°E 24.71'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D6) Found the 1957 monument as described, in good condition, projecting about 2 ft. above ground,
and at record bearing and distance from the remaining BT Cedar South 9 links, in good condition.
The other Cedar BT was not recovered. The monument is substantially at the record position
(intersection of 1/4 lines) and I accept same as a careful and faithful establishment of the
position of the corner.

(D7) Found the monument of record disturbed and out of position, but not damaged. Reestablished the
corner position from three of the four 1998 witnesses of record. Two 1998 W.Pine NBTs are in good
condition (S80°W and N15°W) with measuring nails present. The Spruce NBT N25°E is a stump with the
1998 measuring nail present. The W.Pine S85°E NBT is gone. Reset the 1957 monument at the corner
position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D6) Found 2.5"ID iron pipe.
Set measuring nail with MDNR tag in the side of:
16" Cedar S03°W 6.8' mrkd "CS" 1957 BT
8" Cedar N83°W 18.2' mrkd "CS BT"
14" B.Spruce S86°E 18.6' do
14" Cedar N29°E 22.95' do

(D7) Set 1"ID Iron pipe with 4" brass MI Dept. of
Conservation cap (the 1957 monument).
Found measuring nail in the side of:
14" W.Pine N14°W 29.4' mrkd "1/4S" 1998 NBT
26" W.Pine S82°W 24.9' do do
Set measuring nail with MDNR tag in the side of:
8" B.Spruce S38°W 3.85' mrkd "1/4S NBT"
7" B.Spruce S08°W 53.1' do

Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 10/15/2013

For the Michigan Department of Natural Resources, Forest Resources Division

