

SURVEY &
REMONUMENTATION
OCT 11 1994
COMMISSION

MACKINAC COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located In:

Corner Code =

1. Public Land Survey

T 42N R 1W

A-3

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

RECEIVED & FILED
MACKINAC COUNTY
REGISTER OF DEEDS
SEP 6 1994

Register of Deeds Stamp & File Number

I, James H. Granger, in a field survey on August 9, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1840 original survey set wood post
William Burt 10" cedar S30°W 321ks.
10" cedar N20°W 271ks.

1980 USFS set 2 1/2" pipe w/brass cap
Harold Stockholm set 5 witnesses
#23519

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found USFS monument and 3 witnesses


ACCEPTED BY THE MACKINAC COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 8-16-94

James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

USFS 2 1/2" pipe w/brass cap

wood post north 3'
8" birch S25°W 7.09' Stockholm tag
11" cedar N50°W 22.60' Stockholm tag
11" cedar S56°E 34.76' Stockholm tag
9" cedar N17°E 23.60' tag #16041



Signed by James H. Granger Date August 30, 1994

Surveyor's Michigan License No. 16041 09-06-94 FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

D-0293

REVISED MAY 14, 1975
REVISED JAN., 1983