

LIBER 061660015

B999623

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB


(County)

Located In:  
CLINTON TWP.

Corner Code: #

RECORDED IN MACOMB COUNTY  
RECORDS AT: 8:30 A.M.

DEC 28 1993

  
 CLERK - REGISTER OF DEEDS  
 MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp &amp; File Number

1. Public Land Survey T 2N R 13E D-1  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, BRUCE ANTCLIFF, in a field survey on NOVEMBER 23, 19 93,  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
 expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
 on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
 GLO-Post, NO WITS. REMAIN

ANDERSON, ECKSTEIN, WESTRICK SURVEY NOTES  
 PK&T #30092 W. FACE UTIL POLE, NNE, 59.78  
 PK&T #30092 E. FACE UTIL POLE, SSE, 60.05  
 PK&T #30092 NW FACE UTIL POLE, WSW, 147.14  
 PK&T #30092 NE FACE UTIL POLE, ESE, 180.06

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 FOUND PK NAIL

THERE IS NO OCCUPATION TO HELP VERIFY THIS POINT.  
 THE POINT IS, HOWEVER, WITHIN 0.4' OF BEING ON A SPLIT OF THE DISTANCE BETWEEN  
 C-1 AND E-1, BOTH OF WHICH ARE MONUMENTED, RECORDED CORNERS. IT IS ALSO ON  
 LINE BETWEEN D-13 AND E-13, BOTH OF WHICH ARE ALSO PREVIOUSLY RECORDED.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5/8" REBAR AND CAP #25826; I GUARANTEE TO SET MONUMENTATION CAP AND MON. BOX WHEN  
 THE NEW PAVEMENT IS INSTALLED NEXT YEAR.  
 WITNESSES


FND SWM TAG/PK IN E FACE P POLE, S05E, 60.05'  
 FND SWM TAG/PK IN NW FACE P POLE, S69W, 147.19'  
 FND MDOT TAG/PK ON TOP OF WOOD POST (GUARDRAIL), N74W, 114.99'  
 FND SWM TAG/PK IN NE FACE P POLE, S68E, 180.05'

The selected location is accepted by me and is generally accepted by Professional Surveyors as  
 the best available evidence of the position of the original corner.

Signed by Bruce Antcliff  
 Surveyor's Michigan License No. 25826

Date 12-13-93

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6			5		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

ACCEPTED BY THE MACOMB COUNTY  
 SURVEY PEER GROUP AS THE OFFICIAL  
 CORNER UNDER MICHIGAN PUBLIC ACT 345  
 OF 1990 AT A MEETING HELD ON  
12-1-93  
  
 FRANK J. DeDECKER, P.S., P.E., CHAIRMAN

