

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB
(County)

Located In: WASHINGTON Corner Code #
TOWNSHIP

**SURVEY &
REMONUMENTATION**

FEB 27 1997

COMMISSION

- | | | | |
|---|-------------|--------------|------------|
| 1. Public Land Survey | T <u>4N</u> | R <u>12E</u> | <u>K-4</u> |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling
in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous
Property in Section | S | T | R |
| | S | T | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, field survey on April 12, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 12" Ironwood N64.5°W 31 Links; 10" Ironwood S82°E 21 Links
- 1972-Kobs, PS #14097; LCRC L.2291, Pg.648 - Fnd 3/8" Iron Bar
 - 1979-McMahon, PS #4018; LCRC L.3106, Pg.513 - Fnd?, no witnesses
 - 1972-Kobs, PS #14097; Survey L.2291, Pg.642 - Fnd 3/8" Iron Bar, used same wit as 1972 LCRC
 - 1988-Kobs, PS #14097; Survey L.4375, Pg.846 - Fnd 3/8" Iron Bar, used same wit as 1972 LCRC
 - 1988-Kobs, PS #14097; Survey L.4543, Pg.72 - Fnd 1/2" Iron Bar w/cap #14097, no witnesses
 - 1988-Kobs, PS #14097; Survey L.5390, Pg.227 - Fnd 1/2" Iron Bar w/cap #14097, no witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996 Kennedy Surveying, Inc. - Kennedy, PS #17623 - The corner has not been perpetuated due to the cultivation of the field. There are no lines of occupation extending to the East, West, North & South within 500 feet of this corner.

Certificates of Survey recorded in Liber 4543, Page 72, and Liber 5390, Page 227 were used to recover the corner. I held the angular relationship between the North line and the East of Section 11, recovering the corner 2564.34 feet along the East line of Section 11 from the Northeast corner of Section 11.

FIELD MEASUREMENTS BETWEEN

- K-5 to K-4 GLO = 40 chains or 2640.00 Ft.
K-5 to K-3 GLO = 40 chains or 2640.00 Ft.
K-4 to K-3 2564.34 Ft., L.4543, Pg.72 & L.5390, Pg.227
K-4 to K-3 2563.07 Ft. M.D.O.T.
K-4 to K-5 2537.35 Ft. M.D.O.T., 2535.22 Ft. (GPS-MEA)

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 4-16-96

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


- K-4 I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345" #17623 1 foot below the surface.
North 50.00 feet set 1/2" x 18" Iron Rod w/ID cap 1 foot below the surface
South 50.00 feet set 1/2" x 18" Iron Rod w/ID cap 12" below the surface
East 50.00 feet set 1/2" Iron Rod w/ID cap 12" below the surface
West 50.00 feet set 1/2" Iron Rod w/ID cap 12" below the surface

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date APRIL 24, 1996

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 23, 1975
REVISED JAN., 1983



625