

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 21 N. R. 15 W.	F-11; F-12; F-13
2. PROPERTY CONTROLL- ING IN SECTION 33	T. 21 N. R. 15 W.	11
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 4, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C. (continued)

11
Set 1"x30" pipe & cedar post
w/loc. tag
4" W. Pine N50°E 14.8
4" W. Pine S50°E 13.4

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-11 Reestablished $\frac{1}{4}$ corner on a line from S $\frac{1}{4}$ projected N'y through a point that is on line & equidistant between sec. corners to E&W & in ctr. of E-W b'top co. rd. For all practical purposes this corner was reestablished in ctr. of E-W b'top rd. & equidistant between sec. corners. A straight line position between sec. corners to E&W would be 9.9' S.
- F-12 Established center of Sec. 33 per standard B.L.M. instructions.
- F-13 Found well point as recovered & used by R.L.S. Clint Cole.
- 11 Established center of SW $\frac{1}{4}$ of Sec. 33 per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11	F-12	F-13
Drove $\frac{1}{2}$ "x3/8"x20" iron	Set 1"x3' pipe & cedar post	Found well point & added cedar
13" W. Oak N15°E 53.9	w/loc. tag	post w/loc. tag
5" W. Pine S50°E 56.1	8" W. Pine S65°E 8.9	8" W. Oak N25°W 7.54
5" W. Oak S15°W 38.3	9" W. Pine N80°E 35.3	5" W. Pine N55°E 31.26
Set cedar post w/loc. tag	9" W. Pine S30°W 36.3	N $\frac{1}{4}$ Sec. 5 T20N-R15W
Due S 33'		S87°34'E 164.5

SIGNED BY Carl F. Roser 9-15-76 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

STRONACH TOWNSHIP
MANISTEE COUNTY