

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY. _____ T. 24 N. R. 15 W.		M-6; M-7
2. PROPERTY CONTROLLING IN SECTION 13, T. 24 N. R. 15 W.		4; X 3
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ S. R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 22, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C. (continued)

13  
Set 1"x36" Pipe  
10" Maple S42°E 35.0  
11" Cherry N26°E 67.1  
9" Maple(c1st)N63°E 113.5  
Set cedar post w/loc. tag  
Due E 5'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-6 Found 1½" pipe for east ¼ corner of Sec. 13, as verified by local land owner, Wallace Humphrey. Fence intersection (Fn. W&N) is 11' E of corner. Fence intersection (fn.N-S-W) is 32' E.
- M-7 Recovered 1" pipe; previous Department corner of record.
- 4 Found and accepted concrete mon. as center of NE¼ of Sec. 13, per unrecorded plat of "Sarah J. Acres".
- 13 Established 1/16 corner on line between sec. corners to N & S and on line between center of NW¼ & N-1/16 on N-S¼ line (Sec. 13) to E. This position seems to best fit J.H. Millard split-up of Sec. 13 in 1907.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6	M-7	4
Found 1½" pipe & bolt	Found 1" pipe & post w/loc. tag	Found 4" sq. concrete mon.
12" Maple N07°E 48.92	7" Hemlock S68°W 84.45	w/cedar post & loc. tag
24" Maple S87°E 40.47	10" Twn.Maple S07°E 102.50	Cherry N33°E 59.87
9" Maple S45°E 52.94	9" B. Cherry N61°W 119.00	15" Cherry S17°E 105.45
		4" Cherry S75°W 28.73

SIGNED BY Carl F. Roser 9-4-75 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

PLEASANTON TOWNSHIP  
MANISTEE COUNTY