

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 30W	G12
	T	
	T	
2. Property Controlling in Section	S 36 T 45N R 30W	L12
	S	
	S	
3. Miscellaneous Property in Sec.	S	
	S	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35				
13													

I, Stephan J. Szyszkoski, in a field survey on G12 07/02/2012  
L12 10/10/2011 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G12) Quarter corner common to Sections 33 and 34. 1848 - Established by Wells Burt, Deputy  
Surveyor, midway and on the Section line between Section corners 40.00 chains north and south. Set  
Ironwood post. Sugar 8" S55E 33 links, Sugar 18" N45W 13 links. Found no subsequent record.

(L12) Center of Section 36. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G12) The original post and accessories were not recovered. Found no evidence of the position of the  
original corner on the ground. Reestablished the position for the corner midway and on the Section  
line between Section corners G13 2634.21' south and G11 2634.21' north.

(L12) Established the position for the corner at the intersection of straight lines connecting  
opposite 1/4 corners. From the position thus established, I found a 3/4" iron pin with metal 'T'  
fence post, placed by persons unknown, N17W 52' distant, which I did not accept as marking the  
position for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
5" Sugar N60E 20.8' mrkd "1/4S NBT"  
4" Ironwood S23E 21.4' do  
12" Sugar N74W 12.95' do  
6" Sugar N43W 12.4' do  
Set sq'd Cedar post adjacent.  
Bearings are magnetic.

(L12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
6" Poplar N47E 8.0' mrkd "C1/4 BT"  
6" twin Maple S07W 27.4' do  
8" Poplar S88W 24.8' do  
18" W.Pine N17W 18.0' do  
Set sq'd cedar post adjacent.  
Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 09/06/2012

For the Michigan Department of Natural Resources, Forest Resources Division

