

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 29W T R T R	G5 (GCDB 400500)
2. Property Controlling in Section	S 12 T 48N R 29W S T R S T R	L4 (GCDB 640540)
3. Miscellaneous Property in Sec.	S T R S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on G5 09/30/14
L4 10/13/14 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G5) Corner common to Sections 9-10-15-16. 1848 - Established by Wells Burt, Deputy. Set Cedar
post. Spruce 12" S60°E 39 links, Fir 8" N65°W 33 links. Found no subsequent record.

(L4) Center of Section 12. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G5) The original post and accessories were not recovered. After extensive analysis of the
location of existing corners in this part of the township and of the location of US line calls made
in 1848, I concluded that reliance upon the topographic features noted in the 1848 US field notes
results in the most reasonable position at which to reestablish the corner. Consequently, I
reestablished the position for the corner from the US record to: Stream 20 c.S.W. 5.69 ch. south;
Stream 20 c.S.W. 2.54 ch. east; Enter swamp c.S.W. 1.8 ch. west; Descend ledge 40 ft. c.E&W 39.50
ch. north. The corner is 9 feet east of a straight line between G7 and the Meander cor. on south
side Log Lake between Sec. 3 & 4. The distance south to G7 is 84.3' shorter than the US record of
80.00 chains and is clearly the result of a blunder in the US survey. The distance north to the
Meander corner is 18' shorter than the US record, consistent with deficiencies on N-S lines observed
elsewhere in this township.

(L4) Established the position for the corner at the intersection of straight lines connecting
opposite 1/4 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G5) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
15" Cedar S73°E 30.2' mrkd "S15 NBT"
9" B.Spruce S60°W 31.25' "S16 NBT"
6" B.Spruce N27°E 45.4' "S10 NBT"
10" W.Birch N61°E 40.1' "S10 NBT"
Set sq'd cedar post adjacent.
E= 7928809.063 N= 198389.954

(L4) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
9" B.Spruce S41°W 14.65' mrkd "C1/4 BT"
9" B.Spruce S86°W 14.0' do
4" Balsam N19°W 24.4' do
5" Balsam N30°E 36.75' do
Set sq'd cedar post adjacent.
E= 7932836.046 N= 199155.119

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83 (2011) Datum)
Coord. Ref.=NGS PID AA8080: N= 192972.689 m. E= 7925456.741 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11/24/2014

For the Michigan Department of Natural Resources, Forest Resources Division

