

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 32W	E4
	T R	
	T R	
2. Property Controlling in Section	S 18 T 48N R 32W	16
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4			3		2		1
3													
4	7			8	9	10			11		12		
5													
6	18			17		16			15		14		13
7													
8	19			20		21			22		23		24
9													
10	30			29		28			27		26		25
11													
12	31			32		33			34		35		36
13													

I, Stephan J. Szyszkoski, in a field survey on 16 05/30/2012 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E4) Quarter corner common to Sections 8-9. 1852 - Established by Guy Carleton, Deputy Surveyor, on
the Section line between Section corners 40.00 chains north and south. Set post. Sugar 6" S17E 26
links, Fir 8" N37W 22 links. 1975 - The corner was reestablished by proportionate measurement to the
original record by K.L.Sackett RLS. Set 1"IDx36" pipe with 4" alum. cap. 8" Sugar N71W 22.0', 7"
Sugar S60E 33.0'.

(16-Sec. 18) East 1/16 corner between Sections 18 and 19. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E4) The original post and accessories were not recovered. Found the 1975 monument in good
condition, at an erroneous location, S16E 6.6' from the position intended in 1975. I did not accept
the 1975 position and reestablished the position for the corner midway and on the Section line
between Section corners 2651.18' north and south. I removed the 1975 monument.

(16-Sec. 18) Established the position for the corner midway and on the Section line between Section
corner 1324.06' east and Quarter corner 1324.06' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
4" Sugar N47E 17.75' mrkd "1/4S NBT"
5" Balsam S62E 23.2' do
12" Maple S02W 19.9' do
15" Sugar N81W 19.25' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

(16) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
4" B.Spruce N66E 21.65' mrkd "1/16S BT"
6" Tamarack S27E 16.4' do
12" Cedar S53W 29.8' do
9" B.Spruce N04E 16.05' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 09/12/2012

For the Michigan Department of Natural Resources, Forest Resources Division

