

SURVEY &
REMONUMENTATION

JOB NUMBER: 94030
SHEET NO. : 1-455
For corners in

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY
MICHIGAN
RECEIVED FOR RECORD
1994 DEC 28 PM 5:55

Patricia A. Morley
REGISTER OF DEEDS

	MARQUETTE (County)	Located In:	Corner Code #
1. Public Land Survey		T 48N R 25W	I-7
		T R	
		T R	
		T R	
2. Property Controlling in Section	S T R		
	S T R		
3. Miscellaneous Property in Sec.	S T R		
	S T R		

LIBER 1 PAGE 128
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on Thursday, December 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-7: Section Corner common to Sections 14, 15, 22, and 23, T48N-R25W. 1845: William Ives' original survey notes describe the corner monument as a wood post referenced by: 10" W. Pine S45W, 08 L 6" W. Birch N56E, 25 L 1890: County survey by George P. Cummings indicates S.E. Corner of Section 15 set from Bearing Trees. Distance West 2624'; North 2665'. Cummings Distance South is 2647'.	1987: Charles Clark R.L.S. 25836 found a 1 1/2" iron pin in rock crevice West side Trap Rock Knob in Park Cemetery, 28' +/- East of centerline of paved roadway. 81' +/- North of roadway intersection. 4' +/- above road grade. Referenced by P.K. nails in: 9" W. Birch S10E, 12.18' 14" Maple S25W, 112.21' 5" Maple S65W, 99.31' 8" Maple N17W, 18.98' Note: N.B.T.s not face blazed due to cemetery location (Compass Bearings). L. 5 R.C., P. 104. (See reverse side).
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found and accepted a 1 1/2" iron pipe as referenced in Part A above. Distance South is 2655.84' and Distance North is 2663.40'.

RATIFIED BY PEER GROUP
P.A. 345 OF 1990

Larry J. Bussan
DATE Oct. 17, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994 - Found 1 1/2" iron. Welded 3/4" bolt to iron and attached 3 1/4" diameter aluminum tablet to bolt Marquette County Survey Monument stamped to identify the corner referenced by nails in:

9" White Birch S12E 12.13 ft. Clark NBT (cluster of 3 trees)
17" Maple S24W 111.90 ft. Clark NBT
13" Maple S61W 99.25 ft. Clark NBT
12" Maple N22W 19.0 ft. Clark NBT

Steel sign post West 2.3 ft.

Monument is attached to iron grouted in rock no face blazing was done to NBT's as this corner is in Park Bk. 5, Pg. 73

Signed by


Gerald W. Carlson

Date

12-22-94

Surveyor's Michigan License No.

24589



Record No. 455:

Part "A" Continued:

1991: Certificate of Survey by Glen Van Neste recorded in L. 001, P. 690 indicates a found 1 1/2" iron in rock. No corner accessories given.

1993: Certificate of survey by Glen Van Neste recorded in L. 002, P. 44 indicates a found 1 1/2" iron in rock. No corner accessories given.

1993: Recorded survey by Glen Van Neste recorded in L. 002, P. 45 indicates a found 1 1/2" iron in rock. No corner accessories given.

Rt 6446
Geo
Geo Rem