

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 28W	D5 (GCDB 240500)
2. Property Controlling in Section	S 8 T 50N R 28W	13 (GCDB 260520)
3. Miscellaneous Property in Sec.	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

I, Stephan J. Szyszkoski, in a field survey on 05/20/15 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(13-Sec. 8) Southeast 1/16 corner, Section 8. Not previously monumented.

(D5) Quarter corner common to Sections 8 and 17. 2013 - Lucas S. Tomasoski PS reestablished the position for the corner by proportionate measurement to the original record between Section corners. Set 5/8"x30" capped rebar. 6" R.Oak N60°E 39.50'; 9" R.Pine S51°E 87.73'; 10" J.Pine S08°W 47.28'; 7" R.Oak N65°W 30.81'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(13-Sec. 8) Established the position for the corner at the intersection of straight lines connecting opposite 1/16 corners.

(D5) The 2013 monument and the two northerly NBTs have been destroyed by road construction. Reestablished the position for the corner from the two southerly 2013 witnesses, described below. Verified the position monumented by comparing Mr. Tomasoski's plane coordinates (GPS derived) with my own and found his position to be 0.09'W and 0.03'N of my determination of the coordinates of the position monumented. Both C5 and E5 have been destroyed by road construction and have not been remonumented. The position for the corner falls 11.3' south of the southerly edge of pavement of the newly-paved Co. Rd. AAA. There is a substantial amount of fill at the corner position. It is possible that the 2013 monument may still be in place approx. 3' below the ground surface. I did not excavate the position to investigate this possibility.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(13) Set 1"IDx28" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
5" Balsam N75°E 4.15' mrkd "1/16S BT"
5" Maple S76°E 17.2' do
20" R.Pine S42°W 9.7' do
4" Maple S76°W 10.2' do
Set sq'd cedar post adjacent.
E= 7936687.724 N= 217894.225

(D5) Set 1"IDx28" I.pipe with plastic cap "MI DNR PS 33986". Buried 2" below the ground surface. Existing witnesses:
9" J.Pine S52°E 87.73' fd. nail/tag and blazes
10" J.Pine S08°W 47.28' do
New witnesses:
C/L of "Pass with Care" sign post S80°E 79.1'
10" J.Pine S60°W 59.9' nail/tag. Marked "1/4S NBT"
Set sq'd cedar post adjacent.
E= 7936281.415 N= 217501.576

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum.
Coord. Ref.=NGS PID RK0255: N= 219889.402 m. E= 7928749.670 m.

Signed by Stephan J. Szyszkoski Date 06/04/2015
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Forest Resources Division

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31											36	
13													

