

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 28W	E6
	T R	
	T R	
2. Property Controlling in Section	S 16 T 50N R 28W	9
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 9 09/13/2012 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E6) Quarter corner common to Sections 16 and 17. 1852 - Established by A.B.Wood, Deputy Surveyor,
midway and on the Section line between Section corners 40.00 chains north and south. Set post.
S.Pine 12" S64E 26 links, S.Pine 10" S82W 30 links. Found no subsequent record.

(9-Sec. 16) East 1/16 corner, Section 16. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E6) The original post and accessories were not recovered. At a position N50W 8.9 ft. from the
record position midway between Section corners, I found a 3/4" ID iron pipe, projecting 5" a.g. with
4 nearby trees marked with high and low blazes, with duplex measuring nails in their sides, set by
persons unknown. The nearest tree, a 12" J.Pine S86W 8.85' to nail, has location poster signed by
Rick Penter, Dave Johnson 1988; Mike Roose 4/29/91. Accepted the pipe as the best available evidence
of the position of the original corner.

(9-Sec. 16) Established the position for the corner midway and on a straight line between Quarter
corner 1320.12' east and Center of Section 16 1320.12' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E6) Set 5/8"x24" rebar with plastic MDNR cap
in found 3/4" ID iron pipe.
Found duplex nail in the side of blazed trees:
13" J.Pine S14E 12.45' to nail
11" J.Pine N31W 34.05' to nail
8" J.Pine N52E 27.05' to nail
12" J.Pine S86W 8.85' to nail, w/poster
Set measuring nail with MDNR tag in the side of:
6" J.Pine S82E 25.8' mrkd "1/4S NBT"
Bearings are magnetic. Set post adjacent.

(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
9" W.Pine N03E 4.4' mrkd "1/16S BT"
6" Oak S50E 7.5' do
11" W.Pine S39W 24.0' do
9" Oak S69W 13.1' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 10/08/2012

For the Michigan Department of Natural Resources, Forest Resources Division

